

DMX MEMBRANES LIMITED ACOUSTICAL PERFORMANCE TEST REPORT

SCOPE OF WORK

ASTM E90 AND ASTM E492 TESTING ON DMX 1-STEP 2.0 UNDERLAYMENT WITH LUXURY VINYL PLANK

SPECIMEN TYPE

203 mm Concrete Slab with Suspended Ceiling

REPORT NUMBER

R4958.01-113-11-R0

TEST DATE

07/30/24

ISSUE DATE

08/16/24

RECORD RETENTION END


07/30/28

PAGES

14

DOCUMENT CONTROL

RTTDS-R-AMER-Test-2844 (03/23/22) © 2017 INTERTEK





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0

Date: 08/16/24

REPORT ISSUED TO

DMX MEMBRANES LIMITED

165 Orenda Road Brampton, Ontario L6W 1W3 CANADA

SECTION 1

SCOPE

Architectural Testing, Inc. (an Intertek company) dba Intertek Building & Construction (B&C) was contracted by DMX Membranes Limited to perform testing in accordance with ASTM E90 AND ASTM E492 on DMX 1-Step 2.0 Underlayment with Luxury Vinyl Plank. Results obtained are tested values and were secured by using the designated test methods. Testing was conducted in the VT test chambers at Intertek B&C located in York, Pennsylvania.

This report does not constitute certification of this product nor an opinion or endorsement by this laboratory.

SECTION 2

SUMMARY OF TEST RESULTS

DATA FILE NO.	R4958.01
SERIES/MODEL:	DMX 1-Step 2.0 Underlayment with Luxury Vinyl Plank
STC	63
IIC	73
HIIC	82

COMPLETED BY:	Morgan S. J. Kennedy	REVIEWED BY:	Daniel B. Mohler
	Technician - Acoustical		Project Manager - Acoustical
TITLE:	Testing	TITLE:	Testing
	_		
SIGNATURE:		SIGNATURE:	
DATE:	08/16/24	DATE:	08/16/24

This report is for the exclusive use of Intertek's Client and is provided pursuant to the agreement between Intertek and its Client. Intertek's responsibility and liability are limited to the terms and conditions of the agreement. Intertek assumes no liability to any party, other than to the Client in accordance with the agreement, for any loss, expense or damage occasioned by the use of this report. Only the Client is authorized to permit copying or distribution of this report and then only in its entirety. Any use of the Intertek name or one of its marks for the sale or advertisement of ACCREDITED the tested material, product or service must first be approved in writing by Intertek. The observations and test results in this report are relevant only to the sample(s) tested. This report by itself does not imply that the material, product, or service is or has ever been under an Intertek certification program.

Version: 03/23/22 RTTDS-R-AMER-Test-2844 Page 2 of 14



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0

Date: 08/16/24

SECTION 3

TEST METHODS

The specimen was evaluated in accordance with the following:

ASTM E90-09 (2016), Standard Test Method for Laboratory Measurement of Airborne Sound Transmission Loss of Building Partitions

ASTM E413-22, Classification for Rating Sound Insulation

ASTM E492-22, Standard Test Method for Laboratory Measurement of Impact Sound Transmission Through Floor-Ceiling Assemblies Using the Tapping Machine

ASTM E989-21, Classification for Determination of Impact Insulation Class (IIC)

ASTM E2235-04 (2020), Standard Test Method for Determination of Decay Rates for Use in Sound Insulation Test Methods

ASTM E3207-21, Standard Classification for Determination of Low-Frequency Impact Sound Ratings

ASTM E3222-20, Standard Classification for Determination of High-Frequency Impact Sound Ratings

SECTION 4

MATERIAL SOURCE/INSTALLATION

The full test specimen was assembled on the day of testing by B&C. All materials provided by the client were installed on an existing B&C assembly (203 mm Concrete Slab with Suspended Ceiling) utilizing B&C-supplied materials. The assembly was installed in a steel test frame which was installed into the opening between the source and receive rooms in the test chamber. The test frame was isolated from the structure with dense neoprene gasket.

The total weight of the floor/ceiling assembly was 6130.5 kg. B&C will store samples of the test specimen for four years. Photographs of the test specimen are included in the report. The client did not supply drawings of the test specimen.

B&C will service this report for the entire test record retention period. Test records, such as detailed drawings, datasheets, representative samples of test specimens, or other pertinent project documentation, will be retained by B&C for the entire test record retention period.

Unless differently required, Intertek reports apply the "Simple Acceptance" rule, also called "Shared Risk approach," of ILAC-G8:09/2019, Guidelines on Decision Rules and Statements of Conformity.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0

Date: 08/16/24

SECTION 5

EQUIPMENT

INSTRUMENT	MANUFACTURER	MODEL	DESCRIPTION	ASSET #	CAL DA	ΤE
2-Channel Analog Input	National Instruments	NI 9250	2-Channel Analog Input	INT02672	10/23	*
2-Channel Analog Input	National Instruments	NI 9250	2-Channel Analog Input	INT02673	10/23	*
2-Channel Analog Input	National Instruments	NI 9250	2-Channel Analog Input	INT02674	10/23	*
2-Channel Analog Input	National Instruments	NI 9250	2-Channel Analog Input	INT02675	10/23	*
2-Channel Analog Input	National Instruments	NI 9250	2-Channel Analog Input	INT02676	10/23	*
2-Channel Analog Input	National Instruments	NI 9250	2-Channel Analog Input	INT02677	10/23	*
2-Channel Analog Output	National Instruments	NI 9260	2-Channel Analog Output	INT02611	N/A	*
Microphone Calibrator	Norsonic	34093	Acoustical Calibrator	65105	09/23	
Receive Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	64908	01/24	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	64909	07/24	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	INT02912	03/24	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	64902	09/23	
Receive Room Microphone	PCB Piezotronics	378B20	Microphone and Preamplifier	64910	02/24	
Receive Room Environmental Indicator	Comet	T7510	Temperature and Humidity Transmitter	63810 63811	10/23 10/23	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	64911	09/23	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	64907	01/24	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	INT02256	01/24	
Source Room Microphone	PCB Piezotronics	378C20	Microphone and Preamplifier	INT00235	06/24	
Source Room Microphone	PCB Electronics	378C20	Microphone and Preamplifier	INT00236	06/24	
Source Room Environmental Indicator	Comet	T7510	Temperature and Humidity Transmitter	63812	63812 11/23	
Tapping Machine	Norsonic	Nor277	Tapping Machine	INT03333	02/24	

^{*} The calibration frequency for this equipment is every two years per the manufacturer's recommendation.

VT RECEIVE ROOM VOLUME	155.77 m³
VT SOURCE ROOM VOLUME	190 m ³

SECTION 6

LIST OF OFFICIAL OBSERVERS

NAME	COMPANY
Michael A. Unnone	Intertek B&C
Daniel B. Mohler	Intertek B&C

Version: 03/23/22 Page 4 of 14 RTTDS-R-AMER-Test-2844



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0

Date: 08/16/24

SECTION 7

TEST PROCEDURE

The microphones were calibrated before conducting the tests. The air temperature and relative humidity conditions were monitored and recorded during all measurements. The average temperature and humidity of both the source and receive rooms are listed in Sections 10 and 11. The maximum and minimum temperatures and humidities of the receive room from the duration of the test are listed in Sections 12 and 13.

The airborne transmission loss test was conducted in accordance with the ASTM E90 test method using the single direction method. Two background noise sound pressure level and five sound absorption measurements were conducted at each of five microphone positions. Two sound pressure level measurements were made simultaneously in both rooms, at each of five microphone positions.

The impact sound transmission test was conducted in accordance with the ASTM E492 test method. Two background noise sound pressure level, two sound pressure level measurements with the tapping machine operating at each position specified by ASTM E492, and five sound absorption measurements were conducted at each of five microphone positions.

Detailed test procedures, data for flanking limit tests, repeatability measurements, and reference specimen tests are available upon request.

SECTION 8

TEST CALCULATIONS

The STC (Sound Transmission Class), IIC (Impact Insulation Class), and HIIC (High-Frequency Impact Insulation Class) ratings were calculated in accordance with ASTM E413, ASTM E989, and ASTM E3222, respectively.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0

Date: 08/16/24

SECTION 9

TEST SPECIMEN DESCRIPTION

MATERIAL	DIMENSIONS	THICKNESS	MANUFACTURER AND SERIES	QUANTITY	AVERAGE WEIGHT			
	(mm)	(mm)	SEKIES		WEIGHT			
Luxruy Vinyl	190.5 by 1209	7.0	Lifeproof	10.98 m²	8.15 kg/m²			
Plank	Note: Loose laid							
Hadada	3023 by 1066.8	5.0	DMX 1-Step 2.0	10.98 m²	0.98 kg/m²			
Underlayment	Note: Loose laid							
	3023 by 3632	203.2	5000 PSI	10.98 m²	524.71 kg/m²			
Concrete Slab	25.4 mm from bo	oth the top and bo	to the source room. Mats of ttom of the slab, with bars sp or cracking was visible on th	aced on 305 mm	•			
	38.1 by 2870	43.0	Armstrong HD8906	10.9 lin m	0.45 kg/m			
Drywall Main Beam	Note: Twelve gauge hanger wires were attached to the bottom side of the concrete by Acoutivibe CDC Hangers at twelve locations and then to the main beams. The hanger wire was twisted around itself a minimum of three times within 76 mm creating a 305 mm plenum. The measured steel thickness was 0.5 mm.							
	38.3 by 1219	37.3	Armstrong XL8945P	27.2 lin m	0.45 kg/m			
Cross Tee	Note: Inserted into the main beams on 610 mm centers. The measured steel thickness was 0.5 mm.							
Fiberglass	609.6 by 2438	88.9	Johns Manville Unfaced R- 13	10.98 m²	1.32 kg/m²			
Insulation	Note: Loose laid onto the ceiling grid system							
	3023 by 1219	15.9	National Gypsum Gold Bond® Fire-Shield® Type X	10.56 m²	11.23 kg/m²			
Gypsum Panel	Note: Fastened with 25.4 mm fine thread drywall screws on 305 mm centers							



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0

Date: 08/16/24

SECTION 10

TEST RESULTS - AIRBORNE SOUND TRANSMISSION LOSS



TEST DATE	7/30/2024	30/2024							
DATA FILE NO.	R4958.01	4958.01							
CLIENT	DMX Membrane	MX Membranes Limited							
DESCRIPTION	PSI Concrete Slab, XL8945P Cross Te	mm Lifeproof Luxruy Vinyl Plank, 5 mm DMX 1-Step 2.0 Underlayment, 203.2 mm 5000 ISI Concrete Slab, 43 mm Armstrong HD8906 Drywall Main Beam, 37.3 mm Armstrong (L8945P Cross Tee, 88.9 mm Johns Manville Unfaced R-13 Fiberglass Insulation, 15.9 mm lational Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel, 15.9 mm National							
SPECIMEN AREA	10.98 m ²	Receive Temp.	26.1°C	Source Temp.	24.2°C				
TECHNICIAN	MAU	Receive Humidity	84%	Source Humidity	84%				

FREQ	BACKGROUND	ABSORPTION	SOURCE	RECEIVE	SPECIMEN	95%	NUMBER
FREQ	SPL	ABSORPTION	SPL	SPL	TL	SAMPLING	OF
(Hz)	(dB)	m²	(dB)	(dB)	(dB)	LIMIT	DEFICIENCIES
50	34.2	29.0	93	54	36	2.9	-
63	31.8	23.5	93	52	39	5.1	-
80	33.9	14.6	89	57	31	3.5	-
100	27.4	8.4	85	53	35	2.0	-
125	24.6	9.8	88	48	41	1.6	6
160	26.3	8.2	88	48	43	1.5	7
200	23.1	9.4	88	39	51	1.3	2
250	22.5	9.4	92	41	53	0.7	3
315	18.3	8.5	95	42	55	1.3	4
400	15.3	8.4	95	40	57	0.9	5
500	17.1	7.7	93	35	61	0.9	2
630	15.7	7.7	95	34	64	0.8	0
800	15.2	7.5	96	31	68	0.6	0
1000	17.0	7.7	95	29	69	0.7	0
1250	14.7	7.8	95	29	69	0.5	0
1600	12.5	8.0	95	27	71	0.7	0
2000	10.4	8.6	95	27	70	0.5	0
2500	9.2	9.5	93	25	70	0.5	0
3150	7.9	8.7	92	21	74	0.7	0
4000	8.0	12.8	93	18	75	1.0	0
5000	8.7	16.3	93	14	78	0.9	-
6300	9.3	14.3	87	8	79	0.8	-
8000	9.9	23.3	86	7	76	1.0	-
10000	10.5	23.3	81	8	70	1.3	-
STC Ratir	1g 63	(Sound Transmi	ssion Class)		Sum o	f Deficiencies	29

Notes:

- 1) Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.
- 2) Specimen TL levels listed in $\ensuremath{\textit{red}}$ are potentially limited by the laboratory flanking limit.
- 3) Specimen TL levels listed in <u>blue</u> indicate the lower limit of the transmission loss.
- 4) Specimen TL levels listed in $\ green \ indicate$ that there has been a filler wall correction applied



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0


Date: 08/16/24

SECTION 11

TEST RESULTS - AIRBORNE SOUND TRANSMISSION LOSS GRAPH



TECHNICIAN	MAU	Receive Humidity	84%	Source Humidity	84%			
SPECIMEN AREA	10.98 m ²	Receive Temp.	26.1°C	Source Temp.	24.2°C			
DESCRIPTION	PSI Concrete S XL8945P Cross	7 mm Lifeproof Luxruy Vinyl Plank, 5 mm DMX 1-Step 2.0 Underlayment, 203.2 mm 5000 PSI Concrete Slab, 43 mm Armstrong HD8906 Drywall Main Beam, 37.3 mm Armstrong KL8945P Cross Tee, 88.9 mm Johns Manville Unfaced R-13 Fiberglass Insulation, 15.9 mm National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel, 15.9 mm National						
CLIENT		AX Membranes Limited						
DATA FILE NO.	R4958.01							
TEST DATE	7/30/2024	·						





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0

Date: 08/16/24

SECTION 12



DESCRIPTION	/ IIIIII Liiepiooi	inin Eliephool Edixidy Villyi Flank, 3 min Divix 1-step 2.0 onderlayment, 203.2 min 3000					
	PSI Concrete Sla	PSI Concrete Slab, 43 mm Armstrong HD8906 Drywall Main Beam, 37.3 mm Armstrong					
	XL8945P Cross	XL8945P Cross Tee, 88.9 mm Johns Manville Unfaced R-13 Fiberglass Insulation, 15.9 mm					
	National Gypsu	National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel, 15.9 mm National					
SPECIMEN AREA	10.98 m ² Maximum Temp. 26.1°C Minimum Temp. 26.1°C						
TECHNICIAN	MAU Max. Humidity 84% Min. Humidity 84%						

FREQ	BACKGROUND SPL	ABSORPTION	NORMALIZED IMPACT SPL	95% SAMPLING	NUMBER OF
(Hz)	(dB)	m²	(dB)	LIMIT	DEFICIENCIES
50	35.2	27.4	59	2.0	-
63	38.7	25.2	52	3.1	-
80	34.9	14.4	42	2.6	-
100	27.5	8.6	45	1.4	6
125	24.4	9.4	43	0.9	4
160	21.1	8.2	44	1.1	5
200	17.9	9.4	40	0.5	1
250	14.7	10.1	42	1.2	3
315	17.1	8.9	44	0.7	5
400	15.3	8.2	42	0.4	4
500	15.2	7.7	34	0.8	0
630	16.8	7.8	28	0.6	0
800	16.1	7.5	22	1.0	0
1000	17.1	7.8	18	0.7	0
1250	16.2	7.7	14	0.7	0
1600	14.0	8.0	10	0.7	0
2000	12.1	8.6	9	0.7	0
2500	10.1	9.5	6	0.5	0
3150	8.5	8.7	3	0.5	0
4000	8.3	12.8	4	0.5	-
5000	8.8	16.3	5	0.5	-
6300	9.3	14.3	5	0.5	-
8000	9.9	23.3	8	0.5	-
10000	10.5	23.3	8	0.5	-
IIC Ratin	g 73	(Impact Insulati	ion Class)	Sum of Deficiencies	28

Notes: Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0


Date: 08/16/24

SECTION 13

TEST RESULTS - IMPACT SOUND TRANSMISSION GRAPH



TECHNICIAN	MAU	Max. Humidity	84%	Min. Humidity	84%			
SPECIMEN AREA	10.98 m²	Maximum Temp.	26.1°C	Minimum Temp.	26.1°C			
	XL8945P Cross Te	SI Concrete Slab, 43 mm Armstrong HD8906 Drywall Main Beam, 37.3 mm Armstrong L8945P Cross Tee, 88.9 mm Johns Manville Unfaced R-13 Fiberglass Insulation, 15.9 mm lational Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel, 15.9 mm National						
DESCRIPTION	7 mm Lifeproof L	mm Lifeproof Luxruy Vinyl Plank, 5 mm DMX 1-Step 2.0 Underlayment, 203.2 mm 5000						
CLIENT	DMX Membran	MX Membranes Limited						
DATA FILE NO.	R4958.01				ACCREDITE Testing Laborato			
TEST DATE	7/30/2024	·						





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0

Date: 08/16/24

SECTION 14

TEST RESULTS - HIGH-FREQUENCY IMPACT SOUND TRANSMISSION



TEST DATE	7/30/2024				
DATA FILE NO.	R4958.01				ACCREDITE Testing Laborato
CLIENT	DMX Membranes Limited				
DESCRIPTION	PSI Concrete Slab, XL8945P Cross Te	7 mm Lifeproof Luxruy Vinyl Plank, 5 mm DMX 1-Step 2.0 Underlayment, 203.2 mm 5000 PSI Concrete Slab, 43 mm Armstrong HD8906 Drywall Main Beam, 37.3 mm Armstrong KL8945P Cross Tee, 88.9 mm Johns Manville Unfaced R-13 Fiberglass Insulation, 15.9 mm National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel, 15.9 mm National			
SPECIMEN AREA	10.98 m ²	Maximum Temp.	26.1°C	Minimum Temp.	26.1°C
TECHNICIAN	MAU	Max. Humidity	84%	Min. Humidity	84%

FREQ	BACKGROUND SPL	ABSORPTION	NORMALIZED IMPACT SPL	95% SAMPLE CONFIDENCE	NUMBER OF
(Hz)		m²	(dB)	LIMIT	DEFICIENCIES
400	15.3	8.2	42	0.4	13.0
500	15.2	7.7	34	0.8	5.6
630	16.8	7.8	28	0.6	0.9
800	16.1	7.5	22	1.0	0.0
1000	17.1	7.8	18	0.7	0.0
1250	16.2	7.7	14	0.7	0.0
1600	14.0	8.0	10	0.7	0.0
2000	12.1	8.6	9	0.7	0.0
2500	10.1	9.5	6	0.5	0.0
3150	8.5	8.7	3	0.5	0.0
HIIC Ratio	<mark>ng</mark> 82	(High-Frequency	Impact Insulation Class)	Sum of Deficiencies	19.5

Notes: Receive Room levels less than 5 dB above the Background levels are highlighted in yellow.



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0


Date: 08/16/24

SECTION 15

TEST RESULTS - HIGH-FREQUENCY IMPACT SOUND TRANSMISSION GRAPH



TECHNICIAN	MAU	Max. Humidity	84%	Min. Humidity	84%
SPECIMEN AREA	10.98 m²	Maximum Temp.	26.1°C	Minimum Temp.	26.1°C
	XL8945P Cross Tee, 88.9 mm Johns Manville Unfaced R-13 Fiberglass Insulation, 15 National Gypsum Gold Bond® Fire-Shield® Type X Gypsum Panel, 15.9 mm National			,	
DESCRIPTION	•	7 mm Lifeproof Luxruy Vinyl Plank, 5 mm DMX 1-Step 2.0 Underlayment, 203.2 mm 5000 PSI Concrete Slab, 43 mm Armstrong HD8906 Drywall Main Beam, 37.3 mm Armstrong			
CLIENT	DMX Membra	DMX Membranes Limited			
DATA FILE NO.	R4958.01	ACCRED Testing Labo			
TEST DATE	7/30/2024				





Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0

Date: 08/16/24

SECTION 16

PHOTOGRAPHS



Photo No. 1
Source Room View of Test Specimen Installation



Photo No. 2
Receive Room View of Test Specimen Installation



Telephone: 717-764-7700 Facsimile: 717-764-4129 www.intertek.com/building

TEST REPORT FOR DMX MEMBRANES LIMITED

Report No.: R4958.01-113-11-R0

Date: 08/16/24

SECTION 17

REVISION LOG

REVISION #	DATE	PAGES	DESCRIPTION
RO	08/16/24	N/A	Original Report Issue